

# BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW  
 Date of manufacture :  
 Edition : 30.05.1996  
 Replaces :  
 Test oil : ISO 4113  
 Injection pump : VE5/11E1850L705  
 Type No. : 0 460 415 987  
 Customer Ident.No. :

Customer-specific details  
 Customer : VW

Engine : 2.5 SDI

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar: 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 114

Opening  
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
 x wall thickness > : 2.20  
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444  
 (fuel-delivery  
 actuator) :

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55

Test oil supply  
 temperature > °C : 42...47

Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

Actuator  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 5 and.  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground, Mohms min. : 1.0  
 Connections 3 and 5  
 Mohms min. : 1.0  
 Connections 6 and 7  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 1 and 2  
 Ohms : 4.9...6.5  
 Connections 2 and 3  
 Ohms : 4.9...6.5  
 Connections 1 and 3  
 Ohms : 9.8...13.0

Connections 1 and.  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 4 and 7  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2520  
Setting value, bar : 8.6...8.8

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2520  
Setting value, mm : 11.9...12.7

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2290  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 31.1...31.5  
Dispersion cm<sup>3</sup>/  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1850  
Checkbk. volt  
mV : 3670  
Supply pump  
pressure > bar : 10.4...11.0  
> bar :

2st speed 1/min : 200  
Checkbk. volt  
mV : 2600  
Supply pump  
pressure > bar : 4.5...6.5  
> bar :

Timing device variations:

1st speed 1/min : 200  
Checkbk. volt. mV : 2600  
Timing device  
travel mm : 8.0...12.0  
> mm : (7.0...13.0)  
2nd speed 1/min : 1850  
Checkbk. volt. mV : 3670  
Timing device  
travel mm : 11.8...12.8  
> mm : (11.5...13.1)  
3rd speed 1/min : 1100  
Checkbk. volt. mV : 1800  
Timing device  
travel mm : max. 0.3  
> mm : (max. 1.0)  
Solenoid valve  
Start of  
injection, volts : 12  
4.th speed 1/min : 500  
Checkbk. volt. mV : 2520  
Timing device  
travel mm :  
> mm : (11.5...13.1)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1850  
Checkbk. volt. mV : 3670  
Measuring  
temperature °C : 53  
Overflow : 139...194  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

#### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1850  
Checkbk. volt mV : 3670  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 50.2...52.8  
> 1000s : (49.5...53.5)  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

#### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2290  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (30.0...32.6)  
Dispersion cm³/ :  
> 1000s : (2.5)

#### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2520  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 43.3...45.9  
> 1000s : (42.6...46.6)  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

### Idle delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 400  
Checkbk. volt mV : 1910  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 13.9...17.9  
> 1000s : (12.9...18.9)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

#### Starting fuel delivery:

##### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2690  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 54.0...66.0  
> 1000s : (49.0...71.0)  
Solenoid valve  
Start of  
injection, volts : 12

#### Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 2290  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

#### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

#### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

#### Dimensions for mounting and setting:

##### Description

K	mm	: 3.2...3.4
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Obsereve notes in remark colum

Test sheet : MB  
 Date of manufacture :  
 Edition : 01.05.1996  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE5/11E1900R685

Type No. : 0 460 415 988  
 Customer Ident.No. :

Customer-specific details  
 Customer : Mercedes-Benz

Engine : OM 602 DELA 29

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 116

Opening  
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
 x wall thickness > : 2.20  
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 698  
 (fuel-delivery  
 actuator) : (KDEP 1865/10)

Test line : Prüfkabelset  
 (solenoid valve  
 start of injection): (1 687 011 208)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55

Test oil supply  
 temperature > °C : 42...47

Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

## Actuator

Connections 12 and 13

Test temperature:

15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 13 and.

ground, Mohms min. : 1.0

Connections 12 and

ground, Mohms min. : 1.0

Connections 8 and 13

Mohms min. : 1.0

Connections 12 and 1

Mohms min. : 1.0

## High-pressure compressor sensor

Sensor coils

Connections 8 and 7

Ohms : 4.9...6.5

Connections 6 and 7

Ohms : 4.9...6.5

Connections 6 and 8

Ohms : 9.8...13.0

Connections 6 and.

ground, Mohms min. : 1.0

Connections 7 and

ground, Mohms min. : 1.0

Connections 8 and

ground, Mohms min. : 1.0

Temperature sensor, fuel

Connentions 1 and 2

Test temperature:

15°...30°C, kohms : 1.2...4.0

50°...70°C, kohms : 0.3...1.2

Connections 1 and

ground, Mohms min. : 1.0

Connections 2 and

ground Mohms min. : 1.0

Solenoid valve, start of injection

Connections 1 and 2

Test temperature :

15°...30°C, ohms : 14.3...17.3

50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850



Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2550  
Setting value, bar : 9.3...9.5  
:

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2500  
Setting value, mm : 11.4...12.2  
: (11.0...12.6)

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2500  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/ : 50.8...51.2  
> 1000s : (49.0...53.0)  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1900  
Checkbk. volt  
mV : 3520  
Supply pump  
pressure > bar : 11.3...11.9  
> bar :

2st speed 1/min : 200  
Checkbk. volt  
mV : 2550  
Supply pump  
pressure > bar : 4.5...6.5  
> bar :

Timing device variations:

1st speed 1/min : 1900  
Checkbk. volt. mV : 3520  
Timing device  
travel mm : 11.8...12.8  
> mm : (11.5...13.1)

2nd speed 1/min : 200  
Checkbk. volt. mV : 2550  
Timing device  
travel mm : 3.0...6.0  
> mm : (1.3...7.7)

3rd speed 1/min : 1500  
Checkbk. volt. mV : 1515  
Timing device  
travel mm : 0...3.5  
> mm :

Solenoid valve  
Start of  
injection, volts : 12

4.th speed 1/min : 1100  
Checkbk. volt. mV : 1530  
Timing device  
travel mm : 0...0.5  
> mm : (0...0.8)

Start of  
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1900  
Checkbk. volt. mV : 3570  
Measuring  
temperature °C : 53  
Overflow : 137...192  
> cm<sup>3</sup>/10s : (123...206)

### Fuel delivery variations:

#### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1900  
Checkbk. volt mV : 3520  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 64.1...66.5  
> 1000s : (62.6...68.0)  
Dispersion cm³/ : 2.5  
> 1000s. :

#### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 60  
Speed 1/min : 1000  
Checkbk. volt mV : 3150  
Measuring  
temperature °C : 56  
Fuel delivery cm³/ : 69.7...72.3  
> 1000s : (69.0...73.0)  
Dispersion cm³/ : 2.5  
> 1000s : (4.0)

#### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2550  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 58.6...61.2  
> 1000s : (57.9...61.9)  
Dispersion cm³/ : 3.0  
> 1000s :

### Idle delivery:

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 340  
Checkbk. volt mV : 2000  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 13.6...17.6  
> 1000s : (12.6...18.6)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

### Starting fuel delivery:

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 3060  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 70.0  
> 1000s :  
Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 4020  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

### Dimensions for mounting and setting:

#### Description

K	mm	:
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

# BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : MB  
Date of manufacture :  
Edition : 14.11.1995  
Replaces :  
Test oil : ISO 4113

Injection pump : VE5/11E2000R642

Type No. : 0 460 415 991  
Customer Ident.No. :

Customer-specific details  
Customer : Mercedes-Benz

Engine :

Output kW :  
Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
holder assembly > : 1 688 901 116

Opening  
pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
x wall thickness > : 2.20  
x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 698  
(fuel-delivery  
actuator) :

Test line : Prüfkabelset  
(solenoid valve  
start of injection) : (1 687 011 208)

## TEST PRECONDITIONS

Test oil  
return temp. > °C  
with thermometer : 55

Test oil supply  
temperature > °C : 42...47

Hold-up  
revolutions >1/min : 1200  
Feedback  
voltage mV : 2500

Actuator  
Connections 12 and 13  
Test temperature:  
15°...30°C, ohms : 0.4...1.0  
50°...70°C, ohms : 0.45...1.1

Connections 13 and  
ground, Mohms min. : 1.0  
Connections 12 and  
ground, Mohms min. : 1.0  
Connections 8 and 13  
Mohms min. : 1.0  
Connections 12 and 1  
Mohms min. : 1.0

High-pressure compressor sensor  
Sensor coils  
Connections 8 and 7  
Ohms : 4.9...6.5  
Connections 6 and 7  
Ohms : 4.9...6.5  
Connections 6 and 8  
Ohms : 9.8...13.0

Connections 6 and  
ground, Mohms min. : 1.0  
Connections 7 and  
ground, Mohms min. : 1.0  
Connections 8 and  
ground, Mohms min. : 1.0

Temperature sensor, fuel  
Connections 1 and 2  
Test temperature:  
15°...30°C, kohms : 1.2...4.0  
50°...70°C, kohms : 0.3...1.2

Connections 1 and  
ground, Mohms min. : 1.0  
Connections 2 and  
ground Mohms min. : 1.0

Solenoid valve, start of injection  
Connections 1 and 2  
Test temperature :  
15°...30°C, ohms : 14.3...17.3  
50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2620  
Setting value, bar : 9.3...9.5  
: (9.1...9.7)

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2620  
Setting value, mm : 11.9...12.7  
: (11.0...13.6)

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2520  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 51.3...51.7  
> 1000s : (49.5...53.5)  
Dispersion cm³/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000  
Checkbk. volt  
mV : 3570  
Supply pump  
pressure > bar : 11.5...12.1  
> bar : (11.3...12.3)

2st speed 1/min : 200  
Checkbk. volt  
mV : 2620  
Supply pump  
pressure > bar : 4.5...6.5  
> bar : (4.3...6.7)

Timing device variations:

1st speed 1/min : 2000  
Checkbk. volt. mV : 3570  
Timing device  
travel mm : 11.8...12.8  
> mm : (11.6...13.0)

2nd speed 1/min : 200  
Checkbk. volt. mV : 2620  
Timing device  
travel mm : 8.5...11.5  
> mm : (7.5...12.5)

3rd speed 1/min : 2000  
Checkbk. volt. mV : 1500  
Timing device  
travel mm : 0...3.5  
> mm :

Solenoid valve  
Start of  
injection, volts : 12

4.th speed 1/min : 1100  
Checkbk. volt. mV : 1530  
Timing device  
travel mm : 0...0.6  
> mm : (0...0.8)

Solenoid valve  
Start of  
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1900  
Checkbk. volt. mV : 3570  
Measuring  
temperature °C : 53  
Overflow : 137...192  
> cm³/10s : (123...206)

### Fuel delivery variations:

#### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2000  
Checkbk. volt mV : 3570  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 66.8...69.2  
> 1000s : (65.3...70.7)  
Dispersion cm³/ : 2.5  
> 1000s :

#### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 60  
Speed 1/min : 1000  
Checkbk. volt mV : 3080  
Measuring  
temperature °C : 56  
Fuel delivery cm³/ : 69.3...71.9  
> 1000s : (68.6...72.6)  
Dispersion cm³/ : 4.0  
> 1000s :

#### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2620  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 62.7...65.3  
> 1000s : (62.0...66.0)  
Dispersion cm³/ :  
> 1000s :

### Idle delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 340  
Checkbk. volt mV : 2000  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 13.0...18.0  
> 1000s :  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

#### Starting fuel delivery:

##### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 3110  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 75.6  
> 1000s :

##### Solenoid valve

Start of  
injection, volts : 12

#### Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 4000  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

#### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

#### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

#### Dimensions for mounting and setting:

##### Description

K	mm	:
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

# BOSCH INJECTION PUMP TEST SPECIFICATIONS ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi  
Date of manufacture :  
Edition : 30.05.1994  
Replaces :  
Test oil : ISO 4113

Injection pump : VE5/11E2300L460-1

Type No. : 0 460 415 994  
Customer Ident.No. :

Customer-specific details  
Customer : Audi

Engine : 180-02-TDI-C4

Output kW :  
Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
holder assembly > : 1 688 901 114

Opening  
pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
x wall thickness > : 2.20  
x length > mm : 350

Overflow valve : 2 467 413 009

Test line : 0 986 612 440  
(fuel-delivery  
actuator) :

Test line : 0 986 612 435  
Solenoid valve  
start of injection):

## TEST PRECONDITIONS

Test oil  
return temp. > °C  
with thermometer : 55

Test oil supply  
temperature > °C : 42...47

Hold-up  
revolutions >1/min : 1200  
Feedback  
voltage mV : 2500

Actuator  
Connections 4 and 7  
Test temperature:  
15°...30°C, ohms : 0.4...1.0  
50°...70°C, ohms : 0.45...1.1

Connections 4 and  
ground, Mohms min. : 1.0  
Connections 7 and  
ground, Mohms min. : 1.0  
Connections 2 and 7  
Mohms min. : 1.0  
Connections 4 and 6  
Mohms min. : 1.0

High-pressure compressor sensor  
Sensor coils  
Connections 1 and 3  
Ohms : 4.9...6.5  
Connections 2 and 3  
Ohms : 4.9...6.5  
Connections 1 and 2  
Ohms : 9.8...13.0

Connections 1 and  
ground, Mohms min. : 1.0  
Connections 2 and  
ground, Mohms min. : 1.0  
Connections 3 and  
ground, Mohms min. : 1.0

Temperature sensor, fuel  
Connections 5 and 6  
Test temperature:  
15°...30°C, kohms : 1.2...4.0  
50°...70°C, kohms : 0.3...1.2

Connections 5 and  
ground, Mohms min. : 1.0  
Connections 6 and  
ground Mohms min. : 1.0

Solenoid valve, start of injection  
Connections 1 and 2  
Test temperature :  
15°...30°C, ohms : 14.3...17.3  
50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 750  
Checkbk. volt.  
mV : 3900  
Setting value, bar : 6.0...7.0

Timing device travel:

Speed 1/min : 750  
Checkbk. volt  
mV : 3900  
Setting value, mm : 9.3...9.5

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2125  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2460  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 40.8...41.2  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2125  
Checkbk. volt  
mV : 3900  
Supply pump  
pressure > bar : 7.9...8.9  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3900  
Timing device  
travel mm : 7.5...9.9  
> mm : (7.2...10.2)

2nd speed 1/min : 750  
Checkbk. volt. mV : 3900  
Timing device  
travel mm :  
> mm : (7.5...11.3)

3rd speed 1/min : 1200  
Checkbk. volt. mV : 1800  
Timing device  
travel mm : max. 0.3  
> mm : (max. 2.5)

Solenoid valve  
Start of  
injection, volts : 12

4.th speed 1/min : 2125  
Checkbk. volt. mV : 3900  
Timing device  
travel mm : 11.6...12.6  
> mm : (11.5...12.7)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2125  
Checkbk. volt. mV : 3900  
Measuring  
temperature °C : 53  
Overflow : 97...180  
> cm<sup>3</sup>/10s :

## Fuel delivery variations:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2125  
Checkbk. volt mV : 3910  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 55.7...58.3  
> 1000s : (55.0...59.0)  
Dispersion cm³/ : 3.0  
> 1000s :

2nd temperature-conditioning  
revolution 1/min : 2125  
Checkbk. volt mV : 2500  
Output  
temperature °C : 60  
Speed 1/min : 1000  
Checkbk. volt mV : 3210  
Measuring  
temperature °C : 56  
Fuel delivery cm³/ : 56.8...59.4  
> 1000s : (56.1...60.1)  
Dispersion cm³/ : 3.0  
> 1000s :

3rd temperature-conditioning  
revolution 1/min : 2125  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2460  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (39.7...42.3)  
Dispersion cm³/ :  
> 1000s :

4th temperature-conditioning  
revolution 1/min : 2125  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2320  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 41.9...44.5  
> 1000s : (41.2...45.2)  
Dispersion cm³/ : 3.0  
> 1000s :

## Idle delivery:

1st temperature-conditioning  
revolution 1/min : 2125  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 1520  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 10.2...13.5  
> 1000s : (9.2...15.2)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

## Starting fuel delivery:

1st temperature-conditioning  
revolution 1/min : 2125  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2960  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 79.0  
> 1000s :  
Solenoid valve  
Start of  
injection, volts : 12

## Stop test:

Speed 1/min : 1500  
Checkbk. volt mV : 4125  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Solenoid valve  
Start of  
injection, volts : 12  
  
Shutoff solenoid:  
Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0



Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

Dimensions for mounting and setting:

Description

K	mm	: 2.7...2.9
KF	mm	: 6.5...6.9
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 494

# BOSCH INJECTION PUMP TEST SPECIFICATIONS ELECTRICAL TEST

Observe notes in remark column

Test sheet : MB  
 Date of manufacture :  
 Edition : 05.07.1994  
 Replaces :  
 Test oil : ISO 4113  
 Injection pump : VE5/11E1900R595  
 Type No. : 0 460 415 995  
 Customer Ident.No. :  
 Customer-specific details  
 Customer : Mercedes-Benz  
 Engine : OM 602 DELA 29  
 Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar: 0.30...0.40  
 Calibrating nozzle-holder assembly > : 1 688 901 116  
 Opening pressure > bar : 207...210  
 Test pressure line : 1 680 750 085  
 Outer diameter : 6.00  
 x wall thickness > : 2.20  
 x length > mm : 350  
 Overflow valve : 2 467 413 018  
 Test line : 0 986 612 698  
 (fuel-delivery actuator) :  
 Test line : Prüfkabelset  
 (solenoid valve start of injection): (1 687 011 208)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55  
 Test oil supply  
 temperature > °C : 42...47  
 Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

Actuator  
 Connections 12 and 13  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 13 and ground, Mohms min. : 1.0  
 Connections 12 and ground, Mohms min. : 1.0  
 Connections 8 and 13 Mohms min. : 1.0  
 Connections 12 and 1 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 8 and 7 Ohms : 4.9...6.5  
 Connections 6 and 7 Ohms : 4.9...6.5  
 Connections 6 and 8 Ohms : 9.8...13.0

Connections 6 and ground, Mohms min. : 1.0  
 Connections 7 and ground, Mohms min. : 1.0  
 Connections 8 and ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 1 and 2  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and ground, Mohms min. : 1.0  
 Connections 7 and ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt. : 2430  
mV : 2430  
Setting value, bar : 7.1...7.3  
:

Timing device travel:

Speed 1/min : 500  
Checkbk. volt : 2430  
mV : 2430  
Setting value, mm : 11.6...12.6  
: (10.8...13.4)

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt : 2500  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt : 2360  
mV : 2360  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/ : 43.3...43.7  
> 1000s : (41.7...45.3)  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1900  
Checkbk. volt : 3530  
mV : 3530  
Supply pump  
pressure > bar : 9.0...9.6  
> bar :

2nd speed 1/min : 200  
Checkbk. volt : 2430  
mV : 2430  
Supply pump  
pressure > bar : 4.9...6.9  
> bar :

Timing device variations:

1st speed 1/min : 1900  
Checkbk. volt. mV : 3530  
Timing device  
travel mm : 11.8...12.8  
> mm : (11.5...13.1)

2nd speed 1/min : 200  
Checkbk. volt. mV : 2430  
Timing device  
travel mm : 8.0...11.0  
> mm : (7.0...12.0)

3rd speed 1/min : 1000  
Checkbk. volt. mV : 1460  
Timing device  
travel mm : max. 0.5  
> mm :

Solenoid valve  
Start of  
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1900  
Checkbk. volt. mV : 3530  
Measuring  
temperature °C : 53  
Overflow : 111...167  
> cm<sup>3</sup>/10s : (83...194)

### Fuel delivery variations:

#### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1900  
Checkbk. volt mV : 3530  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 63.8...67.8  
> 1000s : (62.6...68.0)  
Dispersion cm³/ : 2.5  
> 1000s :

#### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 60  
Speed 1/min : 1000  
Checkbk. volt mV : 3120  
Measuring  
temperature °C : 56  
Fuel delivery cm³/ : 69.5...72.1  
> 1000s : (68.8...72.8)  
Dispersion cm³/ : 2.5  
> 1000s : (4.0)

#### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2430  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 53.7...56.3  
> 1000s : (53.0...57.0)  
Dispersion cm³/ : 3.0  
> 1000s :

### Idle delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 340  
Checkbk. volt mV : 1860  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 13.0...17.0  
> 1000s : (12.0...18.0)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

#### Starting fuel delivery:

##### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2880  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 65.0...79.0  
> 1000s : (61.0...83.0)  
Solenoid valve  
Start of  
injection, volts : 12

#### Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 4020  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

#### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

#### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

#### Dimensions for mounting and setting:

##### Description

K	mm	:
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

# BOSCH INJECTION PUMP TEST SPECIFICATIONS ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW  
Date of manufacture :  
Edition : 12.06.1996  
Replaces :  
Test oil : ISO 4113

Injection pump : VE5/11E1750L550

Type No. : 0 460 415 996  
Customer Ident.No. :

Customer-specific details  
Customer : VW

Engine : 2.5 TDI

Output kW :  
Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
holder assembly > : 1 688 901 114

Opening  
pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
x wall thickness > : 2.20  
x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439  
(fuel-delivery  
actuator) : (KDEP 1865/10)

Test line : 0 986 611 983  
(solenoid valve  
start of injection) : (KDEP 1190)

## TEST PRECONDITIONS

Test oil  
return temp. > °C  
with thermometer : 55

Test oil supply  
temperature > °C : 42...47

Hold-up  
revolutions >1/min : 1200  
Feedback  
voltage mV : 2500

Actuator  
Connections 5 and 6  
Test temperature:  
15°...30°C, ohms : 0.4...1.0  
50°...70°C, ohms : 0.45...1.1

Connections 5 and.  
ground, Mohms min. : 1.0  
Connections 6 and  
ground, Mohms min. : 1.0  
Connections 3 and 5  
Mohms min. : 1.0  
Connections 6 and 7  
Mohms min. : 1.0

High-pressure compressor sensor  
Sensor coils  
Connections 1 and 2  
Ohms : 4.9...6.5  
Connections 2 and 3  
Ohms : 4.9...6.5  
Connections 1 and 3  
Ohms : 9.8...13.0

Connections 1 and.  
ground, Mohms min. : 1.0  
Connections 2 and  
ground, Mohms min. : 1.0  
Connections 3 and  
ground, Mohms min. : 1.0

Temperature sensor, fuel  
Connections 4 and 7  
Test temperature:  
15°...30°C, kohms : 1.2...4.0  
50°...70°C, kohms : 0.3...1.2

Connections 4 and  
ground, Mohms min. : 1.0  
Connections 7 and  
ground Mohms min. : 1.0

Solenoid valve, start of injection  
Connections 1 and 2  
Test temperature :  
15°...30°C, ohms : 14.3...17.3  
50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 750  
Checkbk. volt.  
mV : 3900  
Setting value, bar : 6.0...7.0

Timing device travel:

Speed 1/min : 750  
Checkbk. volt  
mV : 3900  
Setting value, mm : 8.5...8.7

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2400  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 36.4...36.8  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1750  
Checkbk. volt  
mV : 3670  
Supply pump  
pressure > bar : 7.4...8.4  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3900  
Timing device  
travel mm : 6.6...9.0  
> mm : (6.3...9.3)  
2nd speed 1/min : 1750  
Checkbk. volt. mV : 3670  
Timing device  
travel mm : 11.6...12.6  
> mm : (11.5...12.7)  
3rd speed 1/min : 1200  
Checkbk. volt. mV : 1800  
Timing device  
travel mm : max. 0.3  
> mm : (max. 2.5)  
Solenoid valve  
Start of  
injection, volts : 12  
4.th speed 1/min : 750  
Checkbk. volt. mV : 3900  
Timing device  
travel mm :  
> mm : (7.4...9.8)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1750  
Checkbk. volt. mV : 3670  
Measuring  
temperature °C : 53  
Overflow : 97...208  
> cm<sup>3</sup>/10s :

## Fuel delivery variations:

### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1750  
Checkbk. volt mV : 3670  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 52.3...54.9  
> 1000s : (51.6...55.6)  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

### 2nd temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1500  
Checkbk. volt mV : 3730  
Measuring  
temperature °C : 53  
Fuel delivery cm³/ : 59.2...62.2  
> 1000s : (57.9...63.5)  
Dispersion cm³/ : 3.5  
> 1000s : (3.5)

### 3rd temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1000  
Checkbk. volt mV : 3210  
Measuring  
temperature °C : 53  
Fuel delivery cm³/ : 55.9...58.5  
> 1000s : (55.2...59.2)  
Dispersion cm³/ : 2.0  
> 1000s : (2.5)

### 4th temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2400  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (35.3...37.9)  
Dispersion cm³/ :  
> 1000s : (2.5)

## 5th temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2320  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 39.5...42.1  
> 1000s : (38.8...42.8)  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

## Idle delivery:

### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 1520  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 6.9...10.9  
> 1000s : (6.9...11.9)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

## Starting fuel delivery:

### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2960  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 74.0...86.0  
> 1000s : (69.0...91.0)

## Solenoid valve

Start of  
injection, volts : 12

## Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 2460  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 5.0

Speed 1/min : 1500  
Checkbk. volt mV : 4100  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0

## Solenoid valve

Start of  
injection, volts : 12

Shutoff solenoid:  
Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

Notes:  
High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

Dimensions for mounting and setting:

Description		
K	mm	: 2.7...2.9
KF	mm	: 6.5...6.9
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 494



# BOSCH INJECTION PUMP TEST SPECIFICATIONS ELECTRICAL TEST

Obsereve notes in remark colum

Test sheet : Volvo PENTA  
Date of manufacture :  
Edition : 21.04.1997  
Replaces :  
Test oil : ISO 4113

Injection pump : VE6/12E1900L749

Type No. : 0 460 426 998  
Customer Ident.No. :

Customer-specific details  
Customer : VOLVO PENTA

Engine : KAD 43

Output kW :  
Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
holder assembly > : 1 688 901 116

Opening  
pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
x wall thickness > : 2.20  
x length > mm : 350

Overflow valve :

Test line : 0 986 612 442  
(fuel-delivery  
actuator) :

Test line : 1 687 011 208  
(solenoid valve  
start of injection): (Test cable set)

Actuator  
Connections 4 and 7  
Test temperature:  
15°...30°C, ohms : 0.4...1.0  
50°...70°C, ohms : 0.45...1.1

Connections 4 and.  
ground, Mohms min. : 1.0  
Connections 7 and  
ground, Mohms min. : 1.0  
Connections 2 and 7  
Mohms min. : 1.0  
Connections 4 and 6  
Mohms min. : 1.0

High-pressure compressor sensor  
Sensor coils  
Connections 1 and 3  
Ohms : 4.9...6.5  
Connections 2 and 3  
Ohms : 4.9...6.5  
Connections 1 and 2  
Ohms : 9.8...13.0

Connections 1 and.  
ground, Mohms min. : 1.0  
Connections 2 and  
ground, Mohms min. : 1.0  
Connections 3 and  
ground, Mohms min. : 1.0

Temperature sensor, fuel  
Connentions 5 and 6  
Test temperature:  
15°...30°C, kohms : 1.2...4.0  
50°...70°C, kohms : 0.3...1,2

Connections 5 and  
ground, Mohms min. : 1.0  
Connections 6 and  
ground Mohms min. : 1.0

Solenoid valve, start of injection  
Connections 1 and 2  
Test temperature :  
15°...30°C, ohms : 14.3...17.3  
50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 800  
Checkbk. volt.  
mV : 2610  
Setting value, bar : 7.2...7.4

Timing device travel:

Speed 1/min : 800  
Checkbk. volt  
mV : 2610  
Setting value, mm : 7.7...8.7

Full-load delivery :

speed 1/min : 800  
Checkbk. volt  
mV : 2610  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 64.2...64.6  
Dispersion cm<sup>3</sup>/ : 5.0  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1900  
Checkbk. volt  
mV : 3500  
Supply pump  
pressure > bar : 7.9...8.9  
> bar :

2st speed 1/min : 500  
Checkbk. volt  
mV : 2730  
Supply pump  
pressure > bar : 5.5...7.9  
> bar :

Timing device variations:

1st speed 1/min : 200  
Checkbk. volt. mV : 2500  
Timing device  
travel mm : 5.9...9.9  
> mm : (5.4...10.4)

2nd speed 1/min : 800  
Checkbk. volt. mV : 2610  
Timing device  
travel mm :  
> mm : (7.5...8.9)

3rd speed 1/min : 1000  
Checkbk. volt. mV : 1660  
Timing device  
travel mm : max. 0.6  
> mm : (max. 0.8)

Solenoid valve

Start of  
injection, volts : 12

4.th speed 1/min : 200  
Checkbk. volt. mV : 2500  
Timing device  
travel mm : 5.9...9.9  
> mm : (5.4...10.4)

Overflow at overflow valve:

speed 1/min : 1900  
Checkbk. volt. mV : 3500  
Overflow : 83...167  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

1<sup>st</sup> Speed 1/min : 1900  
Checkbk. volt mV : 3500  
Fuel delivery cm<sup>3</sup>/ : 78.7...82.3  
> 1000s : (77.0...84.0)  
Dispersion cm<sup>3</sup>/ :  
> 1000s. :

1nd Speed 1/min : 800  
Checkbk. volt mV : 2610  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (61.9...66.9)  
Dispersion cm<sup>3</sup>/ :  
> 1000s : (5.9)

3rd Speed 1/min : 500  
Checkbk. volt mV : 2730  
Fuel delivery cm<sup>3</sup>/ : 80.2...83.2  
> 1000s : (78.7...84.7)  
Dispersion cm<sup>3</sup>/ :  
> 1000s :

### Idle delivery:

Speed 1/min : 400  
Checkbk. volt mV : 1900  
Fuel delivery cm<sup>3</sup>/ : 18.2...24.2  
> 1000s : (16.2...26.2)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 5.0  
> 1000s : (5.0)

### Starting fuel delivery:

Speed 1/min : 100  
Checkbk. volt mV : 2830  
Fuel delivery cm<sup>3</sup>/ : 60.0...82.0  
> 1000s : (51.0...91.0)  
Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 1600  
Checkbk. volt mV : 4000  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ :  
max. 1000s : (max. 3.0)

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10,0  
Rated voltage,  
volts : 12,0

### Dimensions for mounting and setting:

Description		
K	mm	: 2.7...2.9
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

# BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VM  
Date of manufacture :  
Edition : 16.12.1996  
Replaces :  
Test oil : ISO 4113

Injection pump : VE6/12E1900L719

Type No. : 0 460 426 999  
Customer Ident.No. :

Customer-specific details  
Customer : VM-Motori

Engine : D 706 LIM

Output kW :  
Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
holder assembly > : 1 688 901 116

Opening  
pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
x wall thickness > : 2.20  
x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 442  
(fuel-delivery  
actuator) :

Test line : 1 687 011 208  
(solenoid valve  
start of injection): (Test cable set)

## TEST PRECONDITIONS

Test oil  
return temp. > °C  
with thermometer : 55

Test oil supply  
temperature > °C : 42...47

Hold-up  
revolutions >1/min : 1200  
Feedback  
voltage mV : 2500

Actuator  
Connections 4 and 7  
Test temperature:  
15°...30°C, ohms : 0.4...1.0  
50°...70°C, ohms : 0.45...1.1

Connections 4 and  
ground, Mohms min. : 1.0  
Connections 7 and  
ground, Mohms min. : 1.0  
Connections 2 and 7  
Mohms min. : 1.0  
Connections 4 and 6  
Mohms min. : 1.0

High-pressure compressor sensor  
Sensor coils  
Connections 1 and 3  
Ohms : 4.9...6.5  
Connections 2 and 3  
Ohms : 4.9...6.5  
Connections 1 and 2  
Ohms : 9.8...13.0

Connections 1 and  
ground, Mohms min. : 1.0  
Connections 2 and  
ground, Mohms min. : 1.0  
Connections 3 and  
ground, Mohms min. : 1.0

Temperature sensor, fuel  
Connections 5 and 6  
Test temperature:  
15°...30°C, kohms : 1.2...4.0  
50°...70°C, kohms : 0.3...1.2

Connections 5 and  
ground, Mohms min. : 1.0  
Connections 6 and  
ground Mohms min. : 1.0

Solenoid valve, start of injection  
Connections 1 and 2  
Test temperature :  
15°...30°C, ohms : 14.3...17.3  
50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 950  
Checkbk. volt.  
mV : 3250  
Setting value, bar : 7.7...7.9

Timing device travel:

Speed 1/min : 950  
Checkbk. volt  
mV : 3250  
Setting value, mm : 9.3...10.3

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 1940  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 36.5...36.9  
Dispersion cm<sup>3</sup>/ : 3.0  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1900  
Checkbk. volt  
mV : 3780  
Supply pump  
pressure > bar : 8.2...9.6  
> bar :

2st speed 1/min : 200  
Checkbk. volt  
mV : 2230  
Supply pump  
pressure > bar : 4.9...7.3  
> bar :

Timing device variations:

1st speed 1/min : 200  
Checkbk. volt. mV : 2230  
Timing device  
travel mm : 7.0...10.0  
> mm : (6.3...10.7)

2nd speed 1/min : 1900  
Checkbk. volt. mV : 3780  
Timing device  
travel mm : 9.1...10.5  
> mm : (9.0...10.6)

3rd speed 1/min : 950  
Checkbk. volt. mV : 1365  
Timing device  
travel mm : max. 0.4  
> mm : (max. 0.5)

Solenoid valve

Start of  
injection, volts : 12

4.th speed 1/min : 950  
Checkbk. volt. mV : 3250  
Timing device  
travel mm :  
> mm : (9.0...10.6)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1900  
Checkbk. volt. mV : 3780  
Measuring  
temperature °C : 53  
Overflow : 83...194  
> cm<sup>3</sup>/10s :

## Fuel delivery variations:

### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 1900  
Checkbk. volt mV : 3780  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 88.9...93.9  
> 1000s : (88.4...94.4)  
Dispersion cm³/ :  
> 1000s. :

### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 1940  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (35.2...38.2)  
Dispersion cm³/ :  
> 1000s : (3.0)

### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2230  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 56.8...60.8  
> 1000s : (56.3...61.3)  
Dispersion cm³/ :  
> 1000s :

## Idle delivery:

### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 400  
Checkbk. volt mV : 1630  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 5.0...10.0  
> 1000s : (4.5...11.0)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

### Starting fuel delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2760  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 68.0...88.0  
> 1000s : (66.0...90.0)  
Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 1600  
Checkbk. volt mV : 4100  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

### Dimensions for mounting and setting:

#### Description

K	mm	: 2.7...2.9
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : BMW  
 Date of manufacture :  
 Edition : 13.01.1997  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/9E2200R576

Type No. : 0 460 494 995  
 Customer Ident.No. :

Customer-specific details  
 Customer : BMW

Engine : M41

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 022

Opening  
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450

Overflow valve :

Test line : 0 986 612 443  
 (fuel-delivery actuator)

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

Actuator  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 6 and  
 ground, Mohms min. : 1.0  
 Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 3 and 5  
 Mohms min. : 1.0  
 Connections 6 and 7  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 1 and 2  
 kohms : 4.9...6.5  
 Connections 2 and 3  
 kohms : 4.9...6.5  
 Connections 1 and 3  
 kohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 4 and 7  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1500  
Checkbk. volt.  
mV : 2940  
Setting value, bar : 6.9...8.1

Timing device travel:

Speed 1/min : 1500  
Checkbk. volt  
mV : 2940  
Setting value, mm : 11.0...11.2

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 1500  
Checkbk. volt  
mV : 2940  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 47.2...47.6  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2200  
Checkbk. volt  
mV : 3100  
Supply pump  
pressure > bar : 8.1...9.5  
> bar :

2st speed 1/min : 450  
Checkbk. volt  
mV : 2710  
Supply pump  
pressure > bar : 5.1...6.5  
> bar :

Timing device variations:

1st speed 1/min : 450  
Checkbk. volt. mV : 2710  
Timing device  
travel mm : 7.2...9.0  
> mm : (6.8...9.4)

2nd speed 1/min : 1500  
Checkbk. volt. mV : 2940  
Timing device  
travel mm :  
> mm : (10.3...11.9)

3rd speed 1/min : 1500  
Checkbk. volt. mV : 2940  
Timing device  
travel mm : 0.0...0.4  
> mm : (0.0...1.4)

Solenoid valve  
Start of  
injection, volts : 12

4.th speed 1/min : 2200  
Checkbk. volt. mV : 3100  
Timing device  
travel mm : 12.0...12.6  
> mm : (11.8...12.8)

Overflow at overflow valve:

Speed 1/min : 2200  
Checkbk. volt. mV : 3100  
Overflow : 97...180  
> cm<sup>3</sup>/10s :



# Fuel delivery variations:

1. Speed 1/min : 2200  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 51.2...54.2  
> 1000s : (50.2...55.2)  
Dispersion cm<sup>3</sup>/ : 2,5  
> 1000s. :

2. Speed 1/min : 1500  
Checkbk. volt mV : 2940  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (45.6...49.2)  
Dispersion cm<sup>3</sup>/ :  
> 1000s : (3.0)

3. Speed 1/min : 1000  
Checkbk. volt mV : 3060  
Fuel delivery cm<sup>3</sup>/ : 49.1...52.1  
> 1000s : (48.6...52.6)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

4. Speed 1/min : 1000  
Checkbk. volt mV : 2100  
Fuel delivery cm<sup>3</sup>/ : 14.0...17.0  
> 1000s : (13.5...17.5)  
Dispersion cm<sup>3</sup>/ : 2,0  
> 1000s :

5. Speed 1/min : 500  
Checkbk. volt mV : 2710  
Fuel delivery cm<sup>3</sup>/ : 30.3...33.3  
> 1000s : (29.8...33.8)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

# Idle delivery:

Speed 1/min : 450  
Checkbk. volt mV : 2030  
Fuel delivery cm<sup>3</sup>/ : 3.9...6.9  
> 1000s : (2.9...7.9)

Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (3.0)

Starting fuel delivery:  
Speed 1/min : 100  
Checkbk. volt mV : 4020  
Fuel delivery cm<sup>3</sup>/ : 59.9...75.7  
> 1000s : (58.9...76.7)

Solenoid valve  
Start of  
injection, volts : 12

Stop test:  
Speed 1/min : 500  
Checkbk. volt mV : 2710  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ :  
max. 1000s : 3,0

# Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

# Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : IVECO  
 Date of manufacture :  
 Edition : 13.08.1993  
 Replaces :  
 Test oil : ISO 4113  
  
 Injection pump : VE4/9E2100R570  
  
 Type No. : 0 460 494 996  
 Customer Ident.No. :  
  
 Customer-specific details  
 Customer : IVECO  
  
 Engine : Sofim  
 : 8144.97.2580  
  
 Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40  
  
 Calibrating nozzle-  
 holder assembly > : 1 688 901 022  
  
 Opening  
 pressure > bar : 130...133  
  
 Test pressure line : 1 680 750 073  
  
 Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450  
  
 Overflow valve :  
  
 Overflow valve :  
  
 Test line : 0 986 612 434  
 (fuel-delivery actuator)  
  
 Test line : 0 986 612 435  
 (solenoid valve  
 start of injection):

Actuator  
 Connections 4 and 7  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground, Mohms min. : 1.0  
 Connections 2 and 7  
 Mohms min. : 1.0  
 Connections 4 and 6  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 1 and 3  
 kohms : 4.9...6.5  
 Connections 2 and 3  
 kohms : 4.9...6.5  
 Connections 1 and 2  
 kohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000  
Checkbk. volt.  
mV : 3400  
Setting value, bar : 5.8...6.6

Timing device travel:

Speed 1/min : 1000  
Checkbk. volt  
mV : 3400  
Setting value, mm : 9.2...9.4

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 1500  
Checkbk. volt  
mV : 3400  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 67.4...67.8  
Dispersion cm<sup>3</sup>/  
> 1000s : 2.0

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100  
Checkbk. volt  
mV : 3400  
Supply pump  
pressure > bar : 7.4...8.2  
> bar :

2st speed 1/min : 500  
Checkbk. volt  
mV : 3400  
Supply pump  
pressure > bar : 5.1...5.9  
> bar :

3st speed 1/min : 150  
Checkbk. volt  
mV : 3400  
Supply pump  
pressure > bar : min. 3.5  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3400  
Timing device  
travel mm : 6.8...8.2  
> mm : (6.3...8.7)

2nd speed 1/min : 1000  
Checkbk. volt. mV : 3400  
Timing device  
travel mm :  
> mm : (8.3...10.3)

3rd speed 1/min : 2100  
Checkbk. volt. mV : 3400  
Timing device  
travel mm : 11.9...12.7  
> mm : (11.8...12.8)

4.th speed 1/min : 1000  
Checkbk. volt. mV : 2200  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.6)

Solenoid valve

Start of  
injection, volts : 12

Overflow at overflow valve:

Speed 1/min : 2100  
Checkbk. volt. mV : 3400  
Overflow : 83...166  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

1. Speed 1/min : 2100  
Checkbk. volt mV : 3400  
Fuel delivery cm<sup>3</sup>/ : 62.2...66.2  
> 1000s : (61.2...67.2)  
Dispersion cm<sup>3</sup>/ : 3.0  
> 1000s. :

2. Speed 1/min : 1500  
Checkbk. volt mV : 3400  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (65.6...69.6)  
Dispersion cm<sup>3</sup>/ :  
> 1000s :

3. Speed 1/min : 1000  
Checkbk. volt mV : 3400  
Fuel delivery cm<sup>3</sup>/ : 62.3...64.7  
> 1000s : (61.5...65.5)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (3.0)

4. Speed 1/min : 500  
Checkbk. volt mV : 3400  
Fuel delivery cm<sup>3</sup>/ : 51.8...55.4  
> 1000s : (51.3...55.9)  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

### Idle delivery:

Speed 1/min : 450  
Checkbk. volt mV : 2350  
Fuel delivery cm<sup>3</sup>/ : 11.2...14.8  
> 1000s : (10.5...15.5)

Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s : (3.0)

Starting fuel delivery:  
Speed 1/min : 100  
Checkbk. volt mV : 3400  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (42.0...54.0)

Solenoid valve  
Start of  
injection, volts : 12

Stop test:  
Speed 1/min : 750  
Checkbk. volt mV : 3400  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ :  
max. 1000s : (4.0)

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Dimensions for mounting and setting:

#### Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : FIAT  
Date of manufacture :  
Edition : 01.07.1994  
Replaces :  
Test oil : ISO 4113  
  
Injection pump : VE5/9E2250R560  
  
Type No. : 0 460 495 998  
Customer Ident.No. :

Customer-specific details  
Customer : FIAT

Engine : M717 AT 24.C

Output kW :  
Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
holder assembly > : 1 688 901 022

Opening  
pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
x wall thickness > : 2.00  
x length > mm : 450

Overflow valve :

Test line : 0 986 612 434  
(fuel-delivery actuator)

Test line : 0 986 612 435  
(solenoid valve  
start of injection):

## Actuator

Connections 4 and 7

Test temperature:

15°...30°C, ohms : 0.4...1.0

50°...70°C, ohms : 0.45...1.1

Connections 4 and

ground, Mohms min. : 1.0

Connections 7 and

ground, Mohms min. : 1.0

Connections 2 and 7

Mohms min. : 1.0

Connections 4 and 6

Mohms min. : 1.0

## High-pressure compressor sensor

Sensor coils

Connections 1 and 3

kohms : 4.9...6.5

Connections 2 and 3

kohms : 4.9...6.5

Connections 1 and 2

kohms : 9.8...13.0

Connections 1 and

ground, Mohms min. : 1.0

Connections 2 and

ground, Mohms min. : 1.0

Connections 3 and

ground, Mohms min. : 1.0

## Temperature sensor, fuel

Connections 5 and 6

Test temperature:

15°...30°C, kohms : 1.2...4.0

50°...70°C, kohms : 0.3...1.2

Connections 5 and

ground, Mohms min. : 1.0

Connections 6 and

ground Mohms min. : 1.0

## Solenoid valve, start of injection

Connections 1 and 2

Test temperature :

15°...30°C, ohms : 14.3...17.3

50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1250  
Checkbk. volt.  
mV : 3000  
Setting value, bar : 6.6...7.4

Timing device travel:

Speed 1/min : 1250  
Checkbk. volt  
mV : 3000  
Setting value, mm : 7.3...7.5

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 1250  
Checkbk. volt  
mV : 2310  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 34.3...34.7  
Dispersion cm<sup>3</sup>/  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2250  
Checkbk. volt  
mV : 3000  
Supply pump  
pressure > bar : 8.4...9.2  
> bar :

2st speed 1/min : 500  
Checkbk. volt  
mV : 3000  
Supply pump  
pressure > bar : 5.5...6.3  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3000  
Timing device  
travel mm : 5.2...6.4  
> mm : (4.8...6.8)

2nd speed 1/min : 1250  
Checkbk. volt. mV : 3000  
Timing device  
travel mm :  
> mm : (6.6...8.2)

3rd speed 1/min : 2250  
Checkbk. volt. mV : 3000  
Timing device  
travel mm : 9.5...10.1  
> mm : (9.4...10.2)

4.th speed 1/min : 2250  
Checkbk. volt. mV : 1850  
Timing device  
travel mm : max. 2.0  
> mm : (max. 3.0)

Solenoid valve

Start of  
injection, volts : 12

Overflow at overflow valve:

Speed 1/min : 2250  
Checkbk. volt. mV : 3000  
Overflow : 69...125  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

1. Speed 1/min : 2250  
Checkbk. volt mV : 3000  
Fuel delivery cm<sup>3</sup>/ : 62.1...64.7  
> 1000s : (61.4...65.4)  
Dispersion cm<sup>3</sup>/ : 2,0  
> 1000s. :

2. Speed 1/min : 1250  
Checkbk. volt mV : 2310  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (33.0...36.0)  
Dispersion cm<sup>3</sup>/ :  
> 1000s :

3. Speed 1/min : 500  
Checkbk. volt mV : 3000  
Fuel delivery cm<sup>3</sup>/ : 51.5...55.5  
> 1000s : (50.7...55.3)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

### Idle delivery:

Speed 1/min : 400  
Checkbk. volt mV : 1850  
Fuel delivery cm<sup>3</sup>/ : 4.5...7.5  
> 1000s : (3.7...8.3)

Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (3.0)

Starting fuel delivery:  
Speed 1/min : 100  
Checkbk. volt mV : 3290  
Fuel delivery cm<sup>3</sup>/ : 51.0...61.0  
> 1000s : (48.0...64.0)

Solenoid valve  
Start of  
injection, volts : 12

Stop test:  
Speed 1/min : 1000  
Checkbk. volt mV : 3000  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ :  
max. 1000s : 3,0

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Dimensions for mounting and setting:

Description		
K	mm	: 3.2...3.4
KF	mm	:
SVS max.	mm	:
FH	mm	:

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : IVECO  
 Date of manufacture :  
 Edition : 19.01.1994  
 Replaces :  
 Test oil : ISO 4113  
 Injection pump : VE4/11E1900R565  
 Type No. : 0 460 414 996  
 Customer Ident.No. :

Customer-specific details  
 Customer : IVECO

Engine : 840.47.2790

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar: 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 116

Opening  
 pressure > bar : 207...210

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450

Overflow valve : 2 467 413 006

Test line : 0 986 612 434  
 (fuel-delivery  
 actuator) :

Test line : 0 986 612 435  
 (solenoid valve  
 start of injection):

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 45

Test oil supply  
 temperature > °C : 35...40

Hold-up  
 revolutions >1/min : 1100  
 Feedback  
 voltage mV : 2500

## Actuator

Connections 4 and 7

Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground, Mohms min. : 1.0  
 Connections 2 and 7  
 Mohms min. : 1.0  
 Connections 4 and 6  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils

Connections 1 and 3  
 Ohms : 4.9...6.5  
 Connections 2 and 3  
 Ohms : 4.9...6.5  
 Connections 1 and 2  
 Ohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2

Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850



Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 1950  
Setting value, bar : 6.5...7.3

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 1950  
Setting value, mm : 9.30...9.50

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 1900  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 48  
Speed 1/min : 750  
Checkbk. volt  
mV : 2050  
Measuring  
temperature °C : 46  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 39.2...40.2  
Dispersion cm<sup>3</sup>/  
> 1000s : 2.5

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1900  
Checkbk. volt  
mV : 3500  
Supply pump  
pressure > bar : 8.4...9.2  
> bar :

Timing device variations:

1st speed 1/min : 750  
Checkbk. volt. mV : 2050  
Timing device  
travel mm : 9.4...11.4  
> mm : (8.9...11.9)

2nd speed 1/min : 500  
Checkbk. volt. mV : 1950  
Timing device  
travel mm :  
> mm : (8.7...9.7)

3rd speed 1/min : 1900  
Checkbk. volt. mV : 3500  
Timing device  
travel mm : 10.8...12.0  
> mm : (10.6...12.2)

4.th speed 1/min : 1300  
Checkbk. volt. mV : 1850  
Timing device  
travel mm : max. 1.2  
> mm : (max. 3.5)

Solenoid valve

Start of  
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 41  
Speed 1/min : 1900  
Checkbk. volt. mV : 3500  
Measuring  
temperature °C : 43  
Overflow : 83...167  
> cm<sup>3</sup>/10s :

## Fuel delivery variations:

### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 41  
Speed 1/min : 1900  
Checkbk. volt mV : 3500  
Meßtemperatur °C : 43  
Fuel delivery cm³/ : 65.4...68.0  
> 1000s : (64.4...69.0)  
Dispersion cm³/ :  
> 1000s. :

### 2nd temperature-conditioning

revolution 1/min : 1900  
Checkbk. volt mV : 2500  
Output  
temperature °C : 45  
Speed 1/min : 1185  
Checkbk. volt mV : 2170  
Measuring  
temperature °C : 45  
Fuel delivery cm³/ : 36.2...38.8  
> 1000s : (35,2...39.8)  
Dispersion cm³/ : 2.5  
> 1000s :

### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2050  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (38.2...41.2)  
Dispersion cm³/ :  
> 1000s :

### 4rd temperature-conditioning

revolution 1/min : 1900  
Checkbk. volt mV : 2500  
Output  
temperature °C : 45  
Speed 1/min : 900  
Checkbk. volt mV : 2900  
Measuring  
temperature °C : 45  
Fuel delivery cm³/ : 69.0...71.4  
> 1000s : (68.2...72.2)  
Dispersion cm³/ : 2.5  
> 1000s : (3.0)

## Idle delivery:

### 1st temperature-conditioning

revolution 1/min : 1900  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 500  
Checkbk. volt mV : 1360  
Meßtemperatur °C : 49  
Fuel delivery cm³/ : 9.9...14.9  
> 1000s : (8.9...15.9)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

### Starting fuel delivery:

#### 1st temperature-conditioning

revolution 1/min : 1900  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 100  
Checkbk. volt mV : 2870  
Measuring  
temperature °C : 49  
Fuel delivery cm³/ : 67.0  
> 1000s :

#### Solenoid valve

Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 1100  
Checkbk. volt mV : 3500  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

## Dimensions for mounting and setting:

### Description

K	mm	:
KF	mm	: 6.2...6.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : Chrysler  
 Date of manufacture :  
 Edition : 17.07.1996  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2100R707

Type No. : 0 460 404 975  
 Customer Ident.No. :

Customer-specific details  
 Customer : Chrysler

Engine : 424 CLIEE

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 022

Opening  
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450

Overflow valve : 2 467 413 018

Test line : 0 986 612 445  
 (fuel-delivery actuator)

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

## Actuator

Connections 8 and 9

Test temperature:

15°...30°C, ohms : 0.4...1.0

50°...70°C, ohms : 0.45...1.1

Connections 8 and

ground, Mohms min. : 1.0

Connections 9 and

ground, Mohms min. : 1.0

Connections 2 and 8

Mohms min. : 1.0

Connections 7 and 9

Mohms min. : 1.0

## High-pressure compressor sensor

Sensor coils

Connections 1 and 2

kohms : 4.9...6.5

Connections 3 and 2

kohms : 4.9...6.5

Connections 1 and 3

kohms : 9.8...13.0

Connections 1 and

ground, Mohms min. : 1.0

Connections 2 and

ground, Mohms min. : 1.0

Connections 3 and

ground, Mohms min. : 1.0

## Temperature sensor, fuel

Connections 4 and 7

Test temperature:

15°...30°C, kohms : 1.2...4.0

50°...70°C, kohms : 0.3...1.2

Connections 4 and

ground, Mohms min. : 1.0

Connections 7 and

ground Mohms min. : 1.0

## Solenoid valve, start of injection

Connections 1 and 2

Test temperature :

15°...30°C, ohms : 14.3...17.3

50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000  
Checkbk. volt. : 3410  
mV : 3410  
Setting value, bar : 7.1...7.7

Timing device travel:

Speed 1/min : 1000  
Checkbk. volt : 3410  
mV : 3410  
Setting value, mm : 7.2...7.4

Full-load delivery :

Speed 1/min : 1250  
Checkbk. volt : 2320  
mV : 2320  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : 29.8...30.2  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100  
Checkbk. volt : 3130  
mV : 3130  
Supply pump  
pressure > bar : 9.0...9.8  
> bar :

2st speed 1/min : 500  
Checkbk. volt : 2840  
mV : 2840  
Supply pump  
pressure > bar : 6.3...7.1  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 2840  
Timing device  
travel mm : 5.5...6.9  
> mm : (5.2...7.2)

2nd speed 1/min : 1000  
Checkbk. volt. mV : 3410  
Timing device  
travel mm :  
> mm : (7.4...8.2)

3rd speed 1/min : 1500  
Checkbk. volt. mV : 1790  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.8)

Solenoid valve  
Start of  
injection, volts : 12

4st speed 1/min : 500  
Checkbk. volt. mV : 2840  
Timing device  
travel mm : 5.5...6.9  
> mm : (5.2...7.2)

Overflow at overflow valve:

Speed 1/min : 2100  
Checkbk. volt. mV : 3130  
Overflow : 120...175  
> cm<sup>3</sup>/10s : (92...203)

#### Fuel delivery variations:

1. Speed 1/min : 2100  
Checkbk. volt mV : 3130  
Fuel delivery cm<sup>3</sup>/ : 60.5...62.5  
> 1000s : (59.5...63.5)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (2.0)

2. Speed 1/min : 1250  
Checkbk. volt mV : 2320  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (28.7...31.3)  
Dispersion cm<sup>3</sup>/ :  
> 1000s : (3.0)

3. Speed 1/min : 1000  
Checkbk. volt mV : 3410  
Fuel delivery cm<sup>3</sup>/ : 78.3...80.3  
> 1000s : (77.3...81.3)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (2.0)

4. Speed 1/min : 500  
Checkbk. volt mV : 2840  
Fuel delivery cm<sup>3</sup>/ : 44.5...46.5  
> 1000s : (43.5...47.5)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (2.0)

#### Idle delivery:

Speed 1/min : 400  
Checkbk. volt mV : 2110  
Fuel delivery cm<sup>3</sup>/ : 8.5...10.9  
> 1000s : (7.4...12.0)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (3.0)

#### Starting fuel delivery:

Speed 1/min : 100  
Checkbk. volt mV : 3830  
Fuel delivery cm<sup>3</sup>/ : 66.0...76.0  
> 1000s : (63.0...79.0)  
Solenoid valve  
Start of  
injection, volts : 12

#### Stop test:

Speed 1/min : 1500  
Checkbk. volt mV : 4000  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ : max. 3.0  
max. 1000s :

#### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

#### Dimensions for mounting and setting:

##### Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW  
 Date of manufacture :  
 Edition : 16.07.1996  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2075R700

Type No. : 0 460 404 977  
 Customer Ident.No. :

Customer-specific details  
 Customer : VW

Engine : 1.9 TDI

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 114

Opening  
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
 x wall thickness > : 2.20  
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444  
 (fuel-delivery actuator)

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55

Test oil supply  
 temperature > °C : 42...47

Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

Actuator  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground, Mohms min. : 1.0  
 Connections 3 and 5  
 Mohms min. : 1.0  
 Connections 6 and 7  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 1 and 2  
 Ohms : 4.9...6.5  
 Connections 2 and 3  
 Ohms : 4.9...6.5  
 Connections 1 and 3  
 Ohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 4 and 7  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2560  
Setting value, bar : 8.4...9.2

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2510  
Setting value, mm : 10.1...10.3

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 34.7...35.1  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2050  
Checkbk. volt  
mV : 3890  
Supply pump  
pressure > bar : 10.9...11.9  
> bar :

2st speed 1/min : 300  
Checkbk. volt  
mV : 2560  
Supply pump  
pressure > bar : 6.6...8.0  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 2560  
Timing device  
travel mm :  
> mm : (9.2...11.2)  
2nd speed 1/min : 2050  
Checkbk. volt. mV : 3890  
Timing device  
travel mm : 11.8...12.8  
> mm : (11.5...13.1)  
3rd speed 1/min : 1500  
Checkbk. volt. mV : 1500  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.8)  
Solenoid valve  
Start of  
injection, volts : 12  
4.th speed 1/min : 300  
Checkbk. volt. mV : 2560  
Timing device  
travel mm : 5.2...9.2  
> mm : (3.4...11.0)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2050  
Checkbk. volt. mV : 3890  
Measuring  
temperature °C : 53  
Overflow : 138...194  
> cm<sup>3</sup>/10s :

## Fuel delivery variations:

### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2050  
Checkbk. volt mV : 3890  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 49.5...51.9  
> 1000s : (48.9...52.5)  
Dispersion cm³/ : 3.0  
> 1000s. :

### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (33.6...36.2)  
Dispersion cm³/ :  
> 1000s : (2.5)

### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2560  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 41.9...44.5  
> 1000s : (41.2...45.2)  
Dispersion cm³/ : 3.0  
> 1000s :

## Idle delivery:

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 400  
Checkbk. volt mV : 1800  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 9.2...10.2  
> 1000s : (6.7...12.7)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

## Starting fuel delivery:

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2420  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 35.7...45.7  
> 1000s : (32.7...48.7)  
Solenoid valve  
Start of  
injection, volts : 12

## Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 4000  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

## Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

## Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

## Dimensions for mounting and setting:

### Description

K	mm	:
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495



## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW  
 Date of manufacture :  
 Edition : 19.02.1997  
 Replaces :  
 Test oil : ISO 4113  
 Injection pump : VE4/10E2250R590-2  
 Type No. : 0 460 404 978  
 Customer Ident.No. :

Customer-specific details  
 Customer : VW

Engine : 1.9 TDI EDC

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 114

Opening  
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
 x wall thickness > : 2.20  
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439  
 (fuel-delivery  
 actuator) : (KDEP 1865/10)

Test line : 0 986 611 983  
 (solenoid valve  
 start of injection): (KDEP 1190)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55

Test oil supply  
 temperature > °C : 42...47

Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

Actuator  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground, Mohms min. : 1.0  
 Connections 3 and 5  
 Mohms min. : 1.0  
 Connections 6 and 7  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 1 and 2  
 Ohms : 4.9...6.5  
 Connections 2 and 3  
 Ohms : 4.9...6.5  
 Connections 1 and 3  
 Ohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 4 and 7  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2450  
Setting value, bar : 7.3...8.7

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2450  
Setting value, mm : 9.7...9.9

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2420  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 37.2...37.6  
Dispersion cm<sup>3</sup>/ : 2,5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000  
Checkbk. volt  
mV : 4000  
Supply pump  
pressure > bar : 9.7...11.1  
> bar : (9.6...11.2)

2st speed 1/min : 300  
Checkbk. volt  
mV : 2450  
Supply pump  
pressure > bar : 6.5...8.1  
> bar : (6.4...8.2)

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 2450  
Timing device  
travel mm :  
> mm : (8.8...10.8)  
2nd speed 1/min : 2000  
Checkbk. volt. mV : 4000  
Timing device  
travel mm : 11.5...12.9  
> mm : (11.4...13.0)  
3rd speed 1/min : 1400  
Checkbk. volt. mV : 1310  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.8)  
Solenoid valve  
Start of  
injection, volts : 12  
4.th speed 1/min : 300  
Checkbk. volt. mV : 2450  
Timing device  
travel mm : 6.5...9.7  
> mm : (6.1...10.1)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2000  
Checkbk. volt. mV : 4000  
Measuring  
temperature °C : 53  
Overflow : 97...208  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

#### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2000  
Checkbk. volt mV : 4000  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 54.2...57.2  
> 1000s : (53.9...57.5)  
Dispersion cm³/ : 2.5  
> 1000s : (2.5)

#### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2420  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (36.1...38.7)  
Dispersion cm³/ :  
> 1000s : (2.5)

#### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2450  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 43.6...46.6  
> 1000s : (42.8...47.4)  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

### Idle delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 400  
Checkbk. volt mV : 1550  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 6.8...11.8  
> 1000s : (6.3...12,3)  
Solenoid valve.Start of  
injection, volts : 12  
Dispersion cm³/ : 4.0  
> 1000s : (4.0)

#### Starting fuel delivery:

##### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2310  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 36.0...48.0  
> 1000s : (34.0...50.0)  
Solenoid valve  
Start of  
injection, volts : 12

#### Stop test:

Speed 1/min : 750  
Checkbk. volt mV : 3650  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

#### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10,0  
Rated voltage,  
volts : 12,0

#### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

#### Dimensions for mounting and setting:

##### Description

K	mm	:
KF	mm	: 6.2...6.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW  
 Date of manufacture :  
 Edition : 22.05.1996  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2075R696

Type No. : 0 460 404 979  
 Customer Ident.No. :

Customer-specific details  
 Customer : VW

Engine : 1.9 TDI

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 114

Opening  
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
 x wall thickness > : 2.20  
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444  
 (fuel-delivery  
 actuator) :

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55

Test oil supply  
 temperature > °C : 42...47

Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

## Actuator

Connections 5 and 6

Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 5 and.  
 ground, Mohms min. : 1.0

Connections 6 and  
 ground, Mohms min. : 1.0

Connections 3 and 5  
 Mohms min. : 1.0

Connections 6 and 7  
 Mohms min. : 1.0

High-pressure compressor sensor  
Sensor coils

Connections 1 and 2  
 Ohms : 4.9...6.5

Connections 2 and 3  
 Ohms : 4.9...6.5

Connections 1 and 3  
 Ohms : 9.8...13.0

Connections 1 and.  
 ground, Mohms min. : 1.0

Connections 2 and  
 ground, Mohms min. : 1.0

Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
Connections 4 and 7

Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0

Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
Connections 1 and 2

Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2560  
Setting value, bar : 8.4...9.2

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2560  
Setting value, mm : 10.1...10.3

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 34.7...35.1  
Dispersion cm<sup>3</sup>/ : 2,5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2050  
Checkbk. volt  
mV : 3890  
Supply pump  
pressure > bar : 10.9...11.9  
> bar :

2st speed 1/min : 300  
Checkbk. volt  
mV : 2560  
Supply pump  
pressure > bar : 6.6...8.0  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 2560  
Timing device  
travel mm :  
> mm : (9.2...11.2)  
2nd speed 1/min : 2050  
Checkbk. volt. mV : 3890  
Timing device  
travel mm : 11.8...12.8  
> mm : (11.5...13.1)  
3rd speed 1/min : 1500  
Checkbk. volt. mV : 1500  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.8)  
Solenoid valve  
Start of  
injection, volts : 12  
4.th speed 1/min : 300  
Checkbk. volt. mV : 2560  
Timing device  
travel mm : 5.2...9.2  
> mm : (3.4...11.0)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2050  
Checkbk. volt. mV : 3890  
Measuring  
temperature °C : 53  
Overflow : 138...194  
> cm<sup>3</sup>/10s :

## Fuel delivery variations:

### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2050  
Checkbk. volt mV : 3890  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 49.5...51.9  
> 1000s : (48.9...52.5)  
Dispersion cm³/ : 3.0  
> 1000s :

### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (33.6...36.2)  
Dispersion cm³/ :  
> 1000s : (2.5)

### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2560  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 41.9...44.5  
> 1000s : (41.2...45.2)  
Dispersion cm³/ : 3.0  
> 1000s :

## Idle delivery:

### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 400  
Checkbk. volt mV : 1800  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 9.2...10.2  
> 1000s : (6.7...12.7)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

### Starting fuel delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2420  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 35.7...45.7  
> 1000s : (32.7...48.7)  
Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 4000  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

### Dimensions for mounting and setting:

#### Description

K	mm	:
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : Chrysler  
 Date of manufacture :  
 Edition : 10.12.1996  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2100L694

Type No. : 0 460 404 980  
 Customer Ident.No. :

Customer-specific details  
 Customer : Chrysler

Engine : 425 CLIEZ/CLIEF

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar: 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 022

Opening  
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450

Overflow valve : 2 467 413 018

Test line : 0 986 612 445  
 (fuel-delivery actuator)

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

Actuator  
 Connections 8 and 9  
 Test temperature:

15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 8 and  
 ground, Mohms min. : 1.0  
 Connections 9 and  
 ground, Mohms min. : 1.0  
 Connections 2 and 8  
 Mohms min. : 1.0  
 Connections 7 and 9  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils

Connections 1 and 2  
 kohms : 4.9...6.5  
 Connections 3 and 2  
 kohms : 4.9...6.5  
 Connections 1 and 3  
 kohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 4 and 7

Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2

Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000  
Checkbk. volt.  
mV : 3100  
Setting value, bar : 6.4...7.8

Timing device travel:

Speed 1/min : 1000  
Checkbk. volt  
mV : 3100  
Setting value, mm : 6.9...7.1

Full-load delivery :

Speed 1/min : 1250  
Checkbk. volt  
mV : 2270  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 30.6...31.0  
Dispersion cm<sup>3</sup>/  
> 1000s : 2.0

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100  
Checkbk. volt  
mV : 3100  
Supply pump  
pressure > bar : 8.0...9.4  
> bar :

2st speed 1/min : 500  
Checkbk. volt  
mV : 3100  
Supply pump  
pressure > bar : 6.0...7.4  
> bar :

3st speed 1/min : 150  
Checkbk. volt  
mV : 3680  
Supply pump  
pressure > bar : min. 3.5  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3100  
Timing device  
travel mm : 5.2...6.8  
> mm : (5.0...7.0)

2nd speed 1/min : 1000  
Checkbk. volt. mV : 3100  
Timing device  
travel mm :  
> mm : (6.1...7.9)

3rd speed 1/min : 1500  
Checkbk. volt. mV : 1680  
Timing device  
travel mm : max. 0.5  
> mm : (max. 1.5)

Solenoid valve

Start of  
injection, volts : 12

4rd speed 1/min : 2100  
Checkbk. volt. mV : 3100  
Timing device  
travel mm : 9.4...10.2  
> mm : (9.3...10.3)

Overflow at overflow valve:

Speed 1/min : 2100  
Checkbk. volt. mV : 3100  
Overflow : 111...167  
> cm<sup>3</sup>/10s :



### Fuel delivery variations:

1. Speed 1/min : 2100  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 63.5...66.5  
> 1000s : (63.0...67.0)  
Dispersion cm<sup>3</sup>/ :  
> 1000s. :  
  
2. Speed 1/min : 1250  
Checkbk. volt mV : 2270  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (29.5...32.1)  
Dispersion cm<sup>3</sup>/ :  
> 1000s : (3.0)  
  
3. Speed 1/min : 1000  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 66.7...69.7  
> 1000s : (66.2...70.2)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :  
  
4. Speed 1/min : 500  
Checkbk. volt mV : 2660  
Fuel delivery cm<sup>3</sup>/ : 43.4...46.4  
> 1000s : (42.9...46.9)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

### Idle delivery:

Speed 1/min : 400  
Checkbk. volt mV : 2000  
Fuel delivery cm<sup>3</sup>/ : 12.1...15.5  
> 1000s : (11.5...16.1)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (3.0)

### Starting fuel delivery:

Speed 1/min : 100  
Checkbk. volt mV : 3680  
Fuel delivery cm<sup>3</sup>/ : 72.0...82.0  
> 1000s : (69.0...85.0)  
Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 2100  
Checkbk. volt mV : 3100  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ : max. 3.0  
max. 1000s :

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Dimensions for mounting and setting:

#### Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : Ford  
 Date of manufacture :  
 Edition : 19.03.1996  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2100L688

Type No. : 0 460 404 981  
 Customer Ident.No. :

Customer-specific details  
 Customer : Ford

Engine : 425 CLIEF

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 022

Opening  
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450

Overflow valve : 2 467 413 018

Test line : 0 986 612 446  
 (fuel-delivery actuator)

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

## Actuator

Connections 6 and 5

Test temperature:

15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 6 and.

ground, Mohms min. : 1.0

Connections 5 and

ground, Mohms min. : 1.0

Connections 2 and 6

Mohms min. : 1.0

Connections 7 and 5

Mohms min. : 1.0

## High-pressure compressor sensor

Sensor coils

Connections 1 and 2

kohms : 4.9...6.5

Connections 2 and 3

kohms : 4.9...6.5

Connections 1 and 3

kohms : 9.8...13.0

Connections 1 and.

ground, Mohms min. : 1.0

Connections 2 and

ground, Mohms min. : 1.0

Connections 3 and

ground, Mohms min. : 1.0

## Temperature sensor, fuel

Connections 4 and 7

Test temperature:

15°...30°C, kohms : 1.2...4.0

50°...70°C, kohms : 0.3...1.2

Connections 4 and

ground, Mohms min. : 1.0

Connections 7 and

ground Mohms min. : 1.0

## Solenoid valve, start of injection

Connections 1 and 2

Test temperature :

15°...30°C, ohms : 14.3...17.3

50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000  
Checkbk. volt.  
mV : 3100  
Setting value, bar : 6.8...7.4

Timing device travel:

Speed 1/min : 1000  
Checkbk. volt  
mV : 3100  
Setting value, mm : 6.9...7.1

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 1250  
Checkbk. volt  
mV : 2270  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 30.1...30.5  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100  
Checkbk. volt  
mV : 3100  
Supply pump  
pressure > bar : 8.3...9.1  
> bar :

2st speed 1/min : 500  
Checkbk. volt  
mV : 3100  
Supply pump  
pressure > bar : 6.3...7.1  
> bar :

3st speed 1/min : 150  
Checkbk. volt  
mV : 3680  
Supply pump  
pressure > bar : min.. 3.5  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3100  
Timing device  
travel mm : 5.3...6.7  
> mm : (5.0...7.0)

2nd speed 1/min : 1000  
Checkbk. volt. mV : 3100  
Timing device  
travel mm :  
> mm : (6.1...7.9)

3rd speed 1/min : 1500  
Checkbk. volt. mV : 1680  
Timing device  
travel mm : max. 0.5  
> mm : (max. 1.5)

Solenoid valve

Start of  
injection, volts : 12

4.th speed 1/min : 2100  
Checkbk. volt. mV : 3100  
Timing device  
travel mm : 9.5...10.1  
> mm : (9.3...10.3)

Overflow at overflow valve:

Speed 1/min : 2100  
Checkbk. volt. mV : 3100  
Overflow : 83...138  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

1. Speed 1/min : 2100  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 64.0...66.0  
> 1000s : (63.0...67.0)  
Dispersion cm<sup>3</sup>/ :  
> 1000s. :

2. Speed 1/min : 1250  
Checkbk. volt mV : 2270  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (29.0...31.6)  
Dispersion cm<sup>3</sup>/ :  
> 1000s : (3.0)

3. Speed 1/min : 1000  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 67.2...69.2  
> 1000s : (66.2...70.2)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (2.0)

4. Speed 1/min : 500  
Checkbk. volt mV : 2660  
Fuel delivery cm<sup>3</sup>/ : 43.7...45.7  
> 1000s : (42.7...46.7)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (2.0)

### Idle delivery:

Speed 1/min : 400  
Checkbk. volt mV : 2000  
Fuel delivery cm<sup>3</sup>/ : 12.0...14.4  
> 1000s : (10.9...15.5)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s : (3.0)

### Starting fuel delivery:

Speed 1/min : 100  
Checkbk. volt mV : 3680  
Fuel delivery cm<sup>3</sup>/ : 72.0...82.0  
> 1000s : (69.0...85.0)  
Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 2100  
Checkbk. volt mV : 3100  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ : max. 3.0  
max. 1000s :

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Dimensions for mounting and setting:

#### Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW  
 Date of manufacture :  
 Edition : 22.05.1996  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2075R650

Type No. : 0 460 404 984  
 Customer Ident.No. :

Customer-specific details  
 Customer : VW

Engine : 1.9 TDI

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 114

Opening  
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
 x wall thickness > : 2.20  
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444  
 (fuel-delivery  
 actuator) :

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55

Test oil supply  
 temperature > °C : 42...47

Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

Actuator  
 Connections 5 and 6  
 Test temperature:

15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 5 and  
 ground, Mohms min. : 1.0

Connections 6 and  
 ground, Mohms min. : 1.0

Connections 3 and 5  
 Mohms min. : 1.0

Connections 6 and 7  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils

Connections 1 and 2  
 Ohms : 4.9...6.5

Connections 2 and 3  
 Ohms : 4.9...6.5

Connections 1 and 3  
 Ohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0

Connections 2 and  
 ground, Mohms min. : 1.0

Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 4 and 7

Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0

Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2

Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2560  
Setting value, bar : 8.4...9.2

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2560  
Setting value, mm : 10.1...10.3

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 34.7...35.1  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2050  
Checkbk. volt  
mV : 3890  
Supply pump  
pressure > bar : 10.9...11.9  
> bar :

2st speed 1/min : 300  
Checkbk. volt  
mV : 2560  
Supply pump  
pressure > bar : 6.6...8.0  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 2560  
Timing device  
travel mm :  
> mm : (9.2...11.2)  
  
2nd speed 1/min : 2050  
Checkbk. volt. mV : 3890  
Timing device  
travel mm : 11.8...12.8  
> mm : (11.5...13.1)  
  
3rd speed 1/min : 1500  
Checkbk. volt. mV : 1500  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.8)  
Solenoid valve  
Start of  
injection, volts : 12  
  
4.th speed 1/min : 300  
Checkbk. volt. mV : 2560  
Timing device  
travel mm : 5.2...9.2  
> mm : (3.4...11.0)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2050  
Checkbk. volt. mV : 3890  
Measuring  
temperature °C : 53  
Overflow : 138...194  
> cm<sup>3</sup>/10s :

## Fuel delivery variations:

### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2050  
Checkbk. volt mV : 3890  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 49.5...51.9  
> 1000s : (48.9...52.5)  
Dispersion cm³/ : 3.0  
> 1000s. :

### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (33.6...36.2)  
Dispersion cm³/ :  
> 1000s : (2.5)

### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2560  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 41.9...44.5  
> 1000s : (41.2...45.2)  
Dispersion cm³/ : 3.0  
> 1000s :

## Idle delivery:

### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 400  
Checkbk. volt mV : 1800  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 9.2...10.2  
> 1000s : (6.7...12.7)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3.0  
> 1000s : (4.0)

### Starting fuel delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2420  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 35.7...45.7  
> 1000s : (32.7...48.7)  
Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 1000  
Checkbk. volt mV : 4000  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

### Dimensions for mounting and setting:

#### Description

K	mm	: 3,6...3,8
KF	mm	: 8,2...8,6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW  
 Date of manufacture :  
 Edition : 28.10.1996  
 Replaces :  
 Test oil : ISO 4113  
 Injection pump : VE4/10E2250R510-1  
 Type No. : 0 460 404 985  
 Customer Ident.No. :  
 Customer-specific details  
 Customer : Audi  
 Engine : 1.9 TDI  
 Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar: 0,30...0,40  
 Calibrating nozzle-  
 holder assembly > : 1 688 901 114  
 Opening  
 pressure > bar : 207...210  
 Test pressure line : 1 680 750 085  
 Outer diameter : 6,00  
 x wall thickness > : 2,20  
 x length > mm : 350  
 Overflow valve : 2 467 413 018  
 Test line : 0 986 612 439  
 (fuel-delivery  
 actuator) : (KDEP 1865/10)  
 Test line : 0 986 611 983  
 (solenoid valve  
 start of injection): (KDEP 1190)

## TEST PRECONDITIONS

Test oil  
 return temp. > °C  
 with thermometer : 55  
 Test oil supply  
 temperature > °C : 42...47  
 Hold-up  
 revolutions >1/min : 1200  
 Feedback  
 voltage mV : 2500

Actuator  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground, Mohms min. : 1.0  
 Connections 3 and 5  
 Mohms min. : 1.0  
 Connections 6 and 7  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 1 and 2  
 Ohms : 4.9...6.5  
 Connections 2 and 3  
 Ohms : 4.9...6.5  
 Connections 1 and 3  
 Ohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 4 and 7  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850



Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 500  
Checkbk. volt.  
mV : 2245  
Setting value, bar : 6.0...7.4

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2245  
Setting value, mm : 10.7...10.9

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 38.8...39.2  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000  
Checkbk. volt  
mV : 3890  
Supply pump  
pressure > bar : 8.2...9.6  
> bar :

2st speed 1/min : 150  
Checkbk. volt  
mV : 2230  
Supply pump  
pressure > bar : min. 3.5  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 2245  
Timing device  
travel mm :  
> mm : (9.8...11.8)

2nd speed 1/min : 2000  
Checkbk. volt. mV : 3890  
Timing device  
travel mm : 11.5...12.9  
> mm : (11.4...13.0)

3rd speed 1/min : 1400  
Checkbk. volt. mV : 1475  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.8)

Solenoid valve  
Start of  
injection, volts : 12

4.th speed 1/min : 300  
Checkbk. volt. mV : 2245  
Timing device  
travel mm : 8.8...11.6  
> mm : (8.6...11.8)

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2000  
Checkbk. volt. mV : 3890  
Measuring  
temperature °C : 53  
Overflow : 97...180  
> cm<sup>3</sup>/10s : (83...194)

### Fuel delivery variations:

#### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2000  
Checkbk. volt mV : 3890  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 48.2...51.2  
> 1000s : (47.9...51.5)  
Dispersion cm³/ : 2.5  
> 1000s : (2.5)

#### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 60  
Speed 1/min : 750  
Checkbk. volt mV : 2480  
Measuring  
temperature °C : 56  
Fuel delivery cm³/ :  
> 1000s : (37.7...40.3)  
Dispersion cm³/ :  
> 1000s : (2.5)

#### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2245  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 36.8...39.8  
> 1000s : (36.0...40.6)  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

### Idle delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 1600  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 11.7...17.3  
> 1000s : (11.5...17.5)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 3,0  
> 1000s : (4.0)

#### Starting fuel delivery:

##### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2230  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 30.5...42.5  
> 1000s : (28.5...44.5)  
Solenoid valve  
Start of  
injection, volts : 12

#### Stop test:

Speed 1/min : 750  
Checkbk. volt mV : 2480  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0  
Start of

#### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10,0  
Rated voltage,  
volts : 12,0

#### Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

#### Dimensions for mounting and setting:

##### Description

K	mm	:
KF	mm	: 5.8...6.2
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 376

## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : Chrysler  
 Date of manufacture :  
 Edition : 24.03.1997  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2100R635

Type No. : 0 460 404 988  
 Customer Ident.No. :

Customer-specific details  
 Customer : Chrysler

Engine :

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar: 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 022

Opening  
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450

Overflow valve :

Test line : 0 986 612 442  
 (fuel-delivery actuator)

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

Actuator  
 Connections 4 and 7  
 Test temperature:

15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground, Mohms min. : 1.0  
 Connections 2 and 7  
 Mohms min. : 1.0  
 Connections 4 and 6  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils

Connections 1 and 3  
 kohms : 4.9...6.5  
 Connections 2 and 3  
 kohms : 4.9...6.5  
 Connections 1 and 2  
 kohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 5 and 6

Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2

Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000  
Checkbk. volt. : 3100  
Setting value, bar : 6.8...7.4

Timing device travel:

Speed 1/min : 1000  
Checkbk. volt : 3100  
Setting value, mm : 6.9...7.1

Full-load delivery :

Speed 1/min : 1250  
Checkbk. volt : 3100  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 30.1...30.5  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100  
Checkbk. volt : 3100  
Supply pump  
pressure > bar : 8.2...9.0  
> bar :

2st speed 1/min : 500  
Checkbk. volt : 3100  
Supply pump  
pressure > bar : 6.0...6.8  
> bar :

3st speed 1/min : 150  
Checkbk. volt : 3680  
Supply pump  
pressure > bar : min. 3.5  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3100  
Timing device  
travel mm : 5.3...6.7  
> mm : (5.0...7.0)

2nd speed 1/min : 1000  
Checkbk. volt. mV : 3100  
Timing device  
travel mm :  
> mm : (6.1...7.9)

3rd speed 1/min : 1500  
Checkbk. volt. mV : 1680  
Timing device  
travel mm : 0.0...0.5  
> mm : (0.0...1.5)

Solenoid valve

Start of  
injection, volts : 12

Overflow at overflow valve:

Speed 1/min : 2100  
Checkbk. volt. mV : 3100  
Overflow : 56...167  
> cm<sup>3</sup>/10s :

# Fuel delivery variations:

1. Speed 1/min : 2100  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 64.0...66.0  
> 1000s : (63.0...67.0)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s. :

2. Speed 1/min : 1250  
Checkbk. volt mV : 2270  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (29.0...31.6)  
Dispersion cm<sup>3</sup>/ :  
> 1000s : (3.0)

3. Speed 1/min : 1000  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 67.2...69.2  
> 1000s : (66.2...70.2)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

4. Speed 1/min : 500  
Checkbk. volt mV : 2660  
Fuel delivery cm<sup>3</sup>/ : 43.7...45.7  
> 1000s : (42.5...46.5)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

# Idle delivery:

Speed 1/min : 400  
Checkbk. volt mV : 2000  
Fuel delivery cm<sup>3</sup>/ : 12.0...14.2  
> 1000s : (10.9...15.5)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s : (3.0)

Starting fuel delivery:  
Speed 1/min : 100  
Checkbk. volt mV : 3680  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (72.0...82.0)  
Solenoid valve  
Start of  
injection, volts : 12

Stop test:  
Speed 1/min : 2100  
Checkbk. volt mV : 3100  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ : 3.0  
max. 1000s :

# Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

# Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

# BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : Alfa  
 Date of manufacture :  
 Edition : 12.01.1994  
 Replaces :  
 Test oil : ISO 4113

Injection pump : VE4/10E2100L585

Type No. : 0 460 404 991  
 Customer Ident.No. :

Customer-specific details  
 Customer : ALFA

Engine : 425 CHIEA

Output kW :  
 Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-  
 holder assembly > : 1 688 901 022

Opening  
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00  
 x wall thickness > : 2.00  
 x length > mm : 450

Overflow valve :

Test line : 0 986 612 442  
 (fuel-delivery actuator)

Test line : 1 687 011 208  
 (solenoid valve  
 start of injection): (Test cable set)

Actuator  
 Connections 4 and 7  
 Test temperature:  
 15°...30°C, ohms : 0.4...1.0  
 50°...70°C, ohms : 0.45...1.1

Connections 4 and  
 ground, Mohms min. : 1.0  
 Connections 7 and  
 ground, Mohms min. : 1.0  
 Connections 2 and 7  
 Mohms min. : 1.0  
 Connections 4 and 6  
 Mohms min. : 1.0

High-pressure compressor sensor  
 Sensor coils  
 Connections 1 and 3  
 kohms : 4.9...6.5  
 Connections 2 and 3  
 kohms : 4.9...6.5  
 Connections 1 and 2  
 kohms : 9.8...13.0

Connections 1 and  
 ground, Mohms min. : 1.0  
 Connections 2 and  
 ground, Mohms min. : 1.0  
 Connections 3 and  
 ground, Mohms min. : 1.0

Temperature sensor, fuel  
 Connections 5 and 6  
 Test temperature:  
 15°...30°C, kohms : 1.2...4.0  
 50°...70°C, kohms : 0.3...1.2

Connections 5 and  
 ground, Mohms min. : 1.0  
 Connections 6 and  
 ground Mohms min. : 1.0

Solenoid valve, start of injection  
 Connections 1 and 2  
 Test temperature :  
 15°...30°C, ohms : 14.3...17.3  
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000  
Checkbk. volt. : 3100  
mV : 3100  
Setting value, bar : 6.8...7.4

Timing device travel:

Speed 1/min : 1000  
Checkbk. volt : 3100  
mV : 3100  
Setting value, mm : 6.9...7.1

Full-load delivery :

speed 1/min : 1250  
Checkbk. volt : 2270  
mV : 2270  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 30.1...30.5  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100  
Checkbk. volt : 3100  
mV : 3100  
Supply pump  
pressure > bar : 8.2...9.0  
> bar :

2st speed 1/min : 500  
Checkbk. volt : 3100  
mV : 3100  
Supply pump  
pressure > bar : 6.0...6.8  
> bar :

3st speed 1/min : 150  
Checkbk. volt : 3680  
mV : 3680  
Supply pump  
pressure > bar : min. 3.5  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 3100  
Timing device  
travel mm : (5.3...6.7)  
> mm : (5.0...7.0)

2nd speed 1/min : 1000  
Checkbk. volt. mV : 3100  
Timing device  
travel mm :  
> mm : (6.1...7.9)

3rd speed 1/min : 1500  
Checkbk. volt. mV : 1680  
Timing device  
travel mm : 0.0...0.5  
> mm : (0.0...1.5)

Solenoid valve

Start of  
injection, volts : 12

Overflow at overflow valve:

speed 1/min : 2100  
Checkbk. volt. mV : 3100  
Overflow : 56...167  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

Speed 1/min : 2100  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 64.0...66.0  
> 1000s : (63.0...67.0)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s. :

Speed 1/min : 1250  
Checkbk. volt mV : 2270  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : (29.0...31.6)  
Dispersion cm<sup>3</sup>/ :  
> 1000s : (3.0)

Speed 1/min : 1000  
Checkbk. volt mV : 3100  
Fuel delivery cm<sup>3</sup>/ : 67.2...69.2  
> 1000s : (66.2...70.2)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

Speed 1/min : 500  
Checkbk. volt mV : 2660  
Fuel delivery cm<sup>3</sup>/ : 43.7...45.7  
> 1000s : (42.5...46.5)  
Dispersion cm<sup>3</sup>/ : 2.0  
> 1000s :

### Idle delivery:

Speed 1/min : 400  
Checkbk. volt mV : 2000  
Fuel delivery cm<sup>3</sup>/ : 12.0...14.2  
> 1000s : (10.9...15.5)

Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm<sup>3</sup>/ : 2.5  
> 1000s : (3.0)

### Starting fuel delivery:

Speed 1/min : 100  
Checkbk. volt mV : 3680  
Fuel delivery cm<sup>3</sup>/ :  
> 1000s : 72.0...82.0

Solenoid valve  
Start of  
injection, volts : 12

### Stop test:

Speed 1/min : 2100  
Checkbk. volt mV : 3100  
ELAB volts : 0  
Fuel delivery cm<sup>3</sup>/ :  
max. 1000s : 3.0

### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

### Dimensions for mounting and setting:

#### Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:



## BOSCH INJECTION PUMP TEST SPECIFICATIONS

## ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi  
Date of manufacture :  
Edition : 21.04.1993  
Replaces :  
Test oil : ISO 4113

Injection pump : VE4/10E2250R530

Type No. : 0 460 404 992  
Customer Ident.No. :

Customer-specific details  
Customer : Audi

Engine : 1.9 TDI EDC

Output kW :  
Speed 1/min :

## TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40

Calibrating nozzle-  
holder assembly > : 1 688 901 114

Opening  
pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00  
x wall thickness > : 2.20  
x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 440  
(fuel-delivery  
actuator) : (KDEP 1865/10)

Test line : 0 986 611 983  
Solenoid valve  
start of injection) : (KDEP 1190)

## TEST PRECONDITIONS

Test oil  
return temp. > °C  
with thermometer : 55

Test oil supply  
temperature > °C : 42...47

Hold-up  
revolutions >1/min : 1200  
Feedback  
voltage mV : 2500

Actuator  
Connections 4 and 7  
Test temperature:  
15°...30°C, ohms : 0.4...1.0  
50°...70°C, ohms : 0.45...1.1

Connections 4 and  
ground, Mohms min. : 1.0  
Connections 7 and  
ground, Mohms min. : 1.0  
Connections 3 and 4  
Mohms min. : 1.0  
Connections 6 and 7  
Mohms min. : 1.0

High-pressure compressor sensor  
Sensor coils  
Connections 1 and 3  
Ohms : 4.9...6.5  
Connections 2 and 3  
Ohms : 4.9...6.5  
Connections 1 and 2  
Ohms : 9.8...13.0

Connections 1 and  
ground, Mohms min. : 1.0  
Connections 2 and  
ground, Mohms min. : 1.0  
Connections 3 and  
ground, Mohms min. : 1.0

Temperature sensor, fuel  
Connections 5 and 6  
Test temperature:  
15°...30°C, kohms : 1.2...4.0  
50°...70°C, kohms : 0.3...1.2

Connections 5 and  
ground, Mohms min. : 1.0  
Connections 6 and  
ground Mohms min. : 1.0

Solenoid valve, start of injection  
Connections 1 and 2  
Test temperature :  
15°...30°C, ohms : 14.3...17.3  
50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump  
Check values in brackets

Supply pump pressure:

Speed 1/min : 750  
Checkbk. volt.  
mV : 2480  
Setting value, bar : 6.3...6.8

Timing device travel:

Speed 1/min : 500  
Checkbk. volt  
mV : 2245  
Setting value, mm : 9.3...11.7

Full-load delivery :

1st temperature-conditioning  
revolution 1/min : 2000  
Checkbk. volt  
mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt  
mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm<sup>3</sup>/  
> 1000s : 38.8...39.2  
Dispersion cm<sup>3</sup>/  
> 1000s :

Test specifications of injection pump  
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000  
Checkbk. volt  
mV : 3890  
Supply pump  
pressure > bar : 8.6...9.6  
> bar :

2st speed 1/min : 500  
Checkbk. volt  
mV : 2245  
Supply pump  
pressure > bar : 6.2...7.2  
> bar :

3st speed 1/min : 150  
Checkbk. volt  
mV : 2230  
Supply pump  
pressure > bar : min. 3.5  
> bar :

Timing device variations:

1st speed 1/min : 500  
Checkbk. volt. mV : 2245  
Timing device  
travel mm :  
> mm : (8.9...12.1)

2nd speed 1/min : 2000  
Checkbk. volt. mV : 3890  
Timing device  
travel mm : 11.6...12.8  
> mm : (11.4...13.0)

3rd speed 1/min : 1400  
Checkbk. volt. mV : 1475  
Timing device  
travel mm : max. 0.5  
> mm : (max. 0.8)

Solenoid valve  
Start of  
injection, volts : 12

4.th speed 1/min : 300  
Checkbk. volt. mV : 2245  
Timing device  
travel mm : 9.3...11.7  
> mm : (8.9...12.1)

5.th speed 1/min : 150  
Checkbk. volt. mV : 2230  
Timing device  
travel mm : min. 1.5  
> mm :

Overflow at overflow valve:

1st temperature-conditioning  
revolution 1/min : 100  
Checkbk. volt. mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2000  
Checkbk. volt. mV : 3890  
Measuring  
temperature °C : 53  
Overflow : 83...167  
> cm<sup>3</sup>/10s :

### Fuel delivery variations:

#### 1st temperature-conditioning

revolution 1/min : 100  
Checkbk. volt mV : 2500  
Output  
temperature °C : 51  
Speed 1/min : 2000  
Checkbk. volt mV : 3890  
Meßtemperatur °C : 53  
Fuel delivery cm³/ : 48.4...51.0  
> 1000s : (47.9...51.5)  
Dispersion cm³/ : 2.5  
> 1000s : (2.5)

#### 2nd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 750  
Checkbk. volt mV : 2480  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ :  
> 1000s : (37.7...40.3)  
Dispersion cm³/ :  
> 1000s : (2.5)

#### 3rd temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 2245  
Measuring  
temperature °C : 57  
Fuel delivery cm³/ : 36.9...39.5  
> 1000s : (35.9...40.5)  
Dispersion cm³/ : 3.0  
> 1000s : (3.0)

### Idle delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 61  
Speed 1/min : 500  
Checkbk. volt mV : 1600  
Meßtemperatur °C : 57  
Fuel delivery cm³/ : 11.5...16.5  
> 1000s : (11.0...17.0)  
Solenoid valve  
Start of  
injection, volts : 12  
Dispersion cm³/ : 4.0  
> 1000s : (4.0)

#### Starting fuel delivery:

#### 1st temperature-conditioning

revolution 1/min : 2000  
Checkbk. volt mV : 2500  
Output  
temperature °C : 65  
Speed 1/min : 100  
Checkbk. volt mV : 2230  
Measuring  
temperature °C : 61  
Fuel delivery cm³/ : 33.4...43.4  
> 1000s : (30.4...46.4)  
Solenoid valve  
Start of  
injection, volts : 12

#### Stop test:

Speed 1/min : 750  
Checkbk. volt mV : 2480  
ELAB volts : 0  
Fuel delivery cm³/ :  
max. 1000s : 3.0

#### Shutoff solenoid:

Cut-in voltage  
min.> volts : 10.0  
Rated voltage,  
volts : 12.0

Notes:

High-pressure compressor sensor  
Testing only possible with ballast  
EPS 910

Take note of test instructions  
"Distributor pump for direct  
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:	3.6...3.8
KF	mm	:	5.8...6.2
SVS max.	mm	:	
FH	mm	:	
TS		:	1 467 010 376

# ① Test Specifications Fuel Injection Pumps and Governors

40

WPP 001/4 MB 5.7 I

Edition 5.72

PES 6 A 80 C 410 (D)	RS 2085	RSV 575-1100 A7B 533 D (1)	supersedes: 6.70
		RSV 300- 900 A7B 528 (2)	company: Daimler-Benz
		RSV 575-1250 A1B 533 D (3)	engine: OM 352
		RSV 300-1500 A2B 439 D	Mähdrescher: 108 PS (1)
		RSV 300-1100 A2B 439 D	Aggregat: 75 PS (2)
		RSV 600-1100 A4B 439 D	Mähdrescher: 118 PS (3)

All test specifications are valid for Bosch Fuel Injection Pump Test Benches and Testers

## A. Fuel Injection Pump Settings

Port closing at prestroke $2.15 \pm 0.1$ mm (from BDC)						
Rotational speed	Control rod travel	Fuel delivery	Difference	Control rod travel	Fuel delivery	Spring pre-tensioning (torque-control valve)
rev/min	mm	cm <sup>3</sup> /100 strokes	cm <sup>3</sup> /100 strokes	mm	cm <sup>3</sup> /100 strokes	mm
1	2	3	4	2	3	6
1000	6	2.2 - 3.0	0.4			
	9	5.5 - 6.0				
	15	11.5 - 12.8				
200	6	1.3 - 2.2				

Adjust the fuel delivery from each outlet according to the values in

## B. Governor Settings

RSV 575 - 1100 A7B 533 D (1)

Upper rated speed			Intermediate rated speed			Lower rated speed			Sliding sleeve travel Torque-control travel	
Degree of deflection of control lever	rev/min Control rod travel mm	Control rod travel mm rev/min ①	Degree of deflection of control lever	rev/min	Control rod travel mm	Degree of deflection of control lever	rev/min	Control rod travel mm ④	rev/min	Control rod travel mm ③
1	2	3	4	5	6	7	8	9	10	11
ca. 56.5	1100	12.0	without auxiliary spring			ca. 25	575	5.0	1080	0
	1100	7.0					200	19 - 21		
	1120	2.4					575	4.7 - 5.3		
ca. 56	1100	8.2 - 9.4	with auxiliary spring				600	2.8 - 4.0	900	0.1 - 0.3
	1130	3.0 - 4.4					660	0 - 1	650	0.3 - 0.5
	1180	0 - 1								

Torque control travel a = mm

## C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop		Rotational-speed limitation ④	Fuel delivery characteristics		Starting fuel delivery idle switching point		Intermediate rotational speed ⑤a Torque-control travel	
Test oil temp. (°)	②		③a	③b	rev/min	cm <sup>3</sup> /1000 strokes mm RW	rev/min	mm RW
min <sup>-1</sup>	cm <sup>3</sup> /1000 Hübe	min <sup>-1</sup>	rev/min	cm <sup>3</sup> /1000 strokes	rev/min	cm <sup>3</sup> /1000 strokes mm RW	rev/min	mm RW
1	2	3	4	5	6	7	8	9
(20°) 1080	56.5 - 58.5	1100 *	800	54.0 - 57.0	100	13.2 - 13.8	575	5.0
			500	49.0 - 52.0				
(40°) 1060	56.0 - 57.0		800	52.5 - 55.5				
			500	48.0 - 51.0				

Checking values in brackets

\* 1 mm less control rod travel than col. 2

10.75

**BOSCH**

Geschäftsbereich KH. Kundendienst. Kfz-Ausrüstung.  
© by Robert Bosch GmbH, D-7 Stuttgart 1, Postfach 50. Printed in the Federal Republic of Germany.  
Imprimé en République Fédérale d'Allemagne par Robert Bosch GmbH.

Testoil-ISO 4113

D1

## B. Governor Settings

RSV 300-900 A7B 528

(2)

MB 5.7 I

- 2 -

En

Upper rated speed			Intermediate rated speed			Lower rated speed			Sliding sleeve travel	
Degree of deflection of control lever	rev/min Control rod travel mm	Control rod travel mm rev/min ⑤	Degree of deflection of control lever	rev/min	Control rod travel mm	Degree of deflection of control lever	rev/min	Control rod travel mm ④	rev/min	Control rod travel mm ③
1	2	3	4	5	6	7	8	9	10	11
ca. 49.5	900	16.0	without auxiliary spring							
	920	9.6								
	930	4.8								
ca. 48	900	7.5 - 8.0	with auxiliary spring							
	920	2.4 - 3.7								
	950	0 - 1								

RSV 575-1250 A1B 533 D (3)

ca. 62	1250	16.0	without auxiliary spring	ca. 28	575	5.5	1230	0
	1280	11.8			200	19 - 21		
	1320	5.0			575	5.2 - 5.8	650	0.3 - 0.5
ca. 60	1250	ca. 8.5	with auxiliary spring		620	2.0 - 3.6		
	1295	ca. 3.0			700	0 - 1		
	1350	0 - 1						

RSV 300-1500 A2B 439 D

ca. 60	1500	16.0	without auxiliary spring	ca. 22	300	7.5	1480	0
	1550	12.2			150	19 - 21		
	1610	7.0			300	7.2 - 7.8	1200	0.7 - 0.9
	1600	6.2 - 9.0	with auxiliary spring		400	4.7 - 6.6	400	0.9 - 1.1
	1700	1.6 - 2.3			500	3.1 - 5.4		
	1820	0 - 1			800	0 - 1		

RSV 300-1100 A2B 439 D

ca. 43	1100	16.0	without auxiliary spring	ca. 19	300	7.5	1080	0
	1150	12.0			150	19 - 21		
	1190	8.0			300	7.2 - 7.8	800	0 - 0.2
	1180	7.2 - 10.0	with auxiliary spring		500	3.1 - 5.2		
	1250	4.2 - 6.1			760	0 - 1	450	0 - 0.2
	1440	0 - 1						

RSV 600-1100 A4B 439 D

ca. 72	1100	16.0	without auxiliary spring	ca. 44	600	7.5	1080	0
	1150	11.0			100	19 - 21	1000	0.1 - 0.3
	1180	6.8			600	7.2 - 7.8	900	0.5 - 0.7
	1180	5.8 - 8.0	with auxiliary spring		700	3.3 - 5.2	600	0.7 - 0.9
	1200	1.1 - 4.0			850	0 - 1		
	1320	0 - 1						

Torque control travel a = 0 mm

## C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop Test oil temp. (°)		Rotational-speed limitation intermediate speed	Fuel delivery characteristics		Starting fuel delivery idle switching point		Torque-control travel	
rev/min	cm³/1000 strokes	rev/min	rev/min	cm³/1000 strokes	rev/min	cm³/1000 strokes	rev/min	Control rod travel mm
1	2	3	4	5	6	7	8	9
(20°) 880	48.5 - 50.5	900 *			100	13.2 - 13.8		
(2)	48.0 - 50.0							
(40°) 880								
(3)								
(40°) 1230	55.5 - 57.5	1290 - 1300 3 mm RW	800	52.5 - 55.5	100	13.2 - 13.8		
			500	48.0 - 51.0				

Checking values in brackets

\* 1 mm less control rod travel than col. 2

Testoil-ISO 4113